BRUHAT BANGALORE MAHANAGARA PALIKE
RAJARAJESHWARI NAGAR ZONE
WORK ORDER SCHEDULE 'B'

Name of Work : Providing Repairs and to damaged flood lights at JP park play ground in ward 17.

Name of the Agency: Prema Electrical Enterprises

Sl.No	Qty	Description of Item	Unit	Rates as per Sanctioned estimate		Amount
				In figure	In words	
1		Supplying PVC/GI flexible conduit pipe...mm dia fixing on surface over inverted tapered wooden plugs or phill plugs or rawl plugs and clamped using heavy gauge saddles at an interval of 300mm using NF screws and on either end of the pipe terminated completely				
	40	20mm	Mtr	23.00	Rupees Twenty Three Only	920.00
2		Supplying and drawing Flexible Multicore Cable manufactured with electrolytic grade flexible copper with low conductor confirming to table 3 class 5 of IS:8130-1984 and (Virgin) PVC insulation and sheathed suitable for working voltage upto 1100Volts as per IS-694:1990 & confirming to GTP of GROUP-A.				
	120	3C X 2.5Sq.mm	Mtr.	81.60	Rupees Eighty One Only Paise Fifty Nine Only	9792.00
3		Supplying and fixing/replacing condenser for ceiling fan/MV/SV/MH and other luminaries.				
	25	upto 4mfd	Each	104.00	Rupees One Hundred and Four Only	2600.00
4		Supply and fixing of ...Watts heavy duty open construction ferromagnetic copper ballast for HPSV/HPMH lamps				
	15	400Watts	No	3631.00	Rupees Three Thousand Six Hundred and Thirty One Only	54465.00
5		Supplying and fixing of HPMH lamps on existing fitting mounted on tubular pole Single end				
	15	250Watts-400Watts	No	1106.00	Rupees One Thousand One Hundred and Six Only	16590.00
6		Supply and fixing of 230 volts Porcelain holder for MV/SV/MH lamp.				
	25	250-400Watts lamp Holder	No	184.00	Rupees One Hundred and Eighty Four Only	4600.00
7	21	Supplying and fixing/replacement of Ignitor suitable for 70 to 400Watts SV/MH fittings.	No	523.00	Rupees Five Hundred and Twenty Three Only	10983.00
Total						**99950.00**
Tender Premium: -0.25% below						

I Agree to carry Out this work at **-0.25%** Below the rates notified above as per the directions of Engineer incharge of Work

Contractor

Executive Engineer(Electrical)
Rajarajeshwarinagar zone, BBMP